

To: 1100224
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-093-21,191-0000

6-25

NE 1/4 SW, SEC. 14, T. 26 S, R. 37 W

2310 feet from ③ section line

990 feet from ① E section line

TECHNICIAN'S PLUGGING REPORT

Operator License 5952

Lease Name HILLYARD Farms Well # 1

Operator: Amoco Production Co.

County KEARNEY 168.68

Name & Address P.O. Box 800 Room 936 B

Well Total Depth 5190 feet

DENVEN CO. 80201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1750

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON License Number NA

Address Liberal, KS

Company to plug at: Hour: 9:00 AM Day: 25 Month: JUNE Year: 19 98

Plugging proposal received from DEAN L. TINSLEY

(company name) Amoco Production Co. (phone) 316-356-6981

core: 5 1/2" @ 4224' w/ 580 sks. circ to surface PSTP: 4006' Pay @ 3986-4018

1st PUMP 25SX class C w/ 25X cotton seed hulls displaced RECEIVED 1900:31Q1

2nd Mix + pump 150SX class C

3rd check BACKSIDE for Cement

DU for 4224 - east circ to Surg.

RECEIVED
JUL 10 1998
7-10-98
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by GARY WINTERS
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour 10:00 AM Day: 25 Month: 06 Year: 19 98

ACTUAL PLUGGING REPORT MIX + PUMPED 200# cotton seed hulls w/ 25SX class C

Cement, displaced pill to 4006' w/ 9.0 # mud. 2nd plug: mix + pump

155 SX class C cement - fill casing from 3' to 1900'

3rd checked annulus, pumped 35SX cement, shut-in w/ 500 lbs.

Remarks: 65/35 Pre mix 6% gel (class C cement by Halliburton Cementing Co.)

(If additional description is necessary, use BACK of this form.)

INVOICED
DATE JUL 13 1998
INV. NO. 50897

Signed Gary Winters
(TECHNICIAN)