

To: 040678 8-2
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 093-21,222-0000 150
S/2 SE NW, SEC. 3, T. 24 S, R. 37 W/EX
2970 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363
Operator: BEREXCO INC.
Name &
Address 970 Fourth Financial Ctr.
Wichita, KS 67202

Lease Name Branine Well # 1-3
County Kearny 165.75
Well Total Depth 5100 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1645

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor BEREDCO INC. License Number 5147
Address 401 E. Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 8 p.m. Day: 1 Month: 8 Year: 19 92

Plugging proposal received from Kent
(company name) BEREDCO INC. (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 2900' with 100 sx cement, 2nd plug at 1675' with 50 sx cement,
3rd plug at 750' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:15 a.m. Day: 2 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2900' with 100. sx cement,
2nd plug at 1675' with 50 sx cement,
3rd plug at 750' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 7 1992 8792

Remarks: Used 60/40 Pozmix 6% gel by HOWCO.
(If additional description is necessary, use BACK of this form.)

INVOICED
(Date) (old date) observe this plugging.

DATE 9-11-92
INV. NO. 36086

Signed Stephen J. Pfeifer
(TECHNICIAN)