

5-10 15-093-00461-0000

52

To: 1 090079
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-N/A
NE NE SW, SEC. 35, T 24 S, R 36 W
2390 feet from S section line
2740 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5447
Operator: OXY USA Inc.
Name & Address: P.O. Box 26100
Oklahoma City, OK 73126-0100

Lease Name Beymer A Well # 1
County Kearny 85.63
Well Total Depth 2635 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 800

Abandoned Oil Well Gas Well X Input Well SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor OXY USA License Number 5447

Address P.O. Box 26100, Oklahoma City, OK 73126-0100

Company to plug at: Hour: 9:30 a.m. Day: 10 Month: 5 Year: 19 91

Plugging proposal received from Russ Cravens

(company name) OXY USA (phone) 316-675-2293

were: 5 1/2" at 2634' with 900 sx cement, PBTD 2609', Perfs at 2352-2586' (6 sets)

1st plug set CIBP at 2300'

2nd plug run in with tubing to 1945', spot 68 sx cement from 1945' to 1335' from surface,

3rd plug pull to 1365', spot 68 sx cement from 1365-765' from surface,

4th plug pull to 775', fill 5 1/2" to surface with cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:30 a.m. Day: 10 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2300'

2nd plug ran in with tubing to 1945', spotted 68 sx cement from 1945-1335' from surface,

3rd plug pulled to 1365', spotted 68 sx cement from 1365-765' from surface,

4th plug pulled to 775', filled 5 1/2" to surface with cement.

Checked backside at 600 psi.

RECEIVED
STATE CORPORATION COMMISSION
5-19-91
MAY 14 1991

Remarks: Used Class H cement by Dowell. No casing recovery. (if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE 5-29-91

INV. NO. 31946

5-10 SEP 27 1991