

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009-23, 198000

SE. NE. SE., SEC. 14, T. 16 S, R. 11 W E

1650 FEET FROM N/S SECTION LINE

330 FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 6393

LEASE NAME MARMIE WELL # 1

OPERATOR: BROUGHNER OIL INC.
NAME & ADDRESS P.O. DRAWER 1367
GREAT BEND, Mo.
67530

COUNTY BARTON

WELL TOTAL DEPTH 3435 FEET \$ 111.64

CONDUCTOR PIPE: SIZE 0 FEET

SURFACE CASING: SIZE 8 5/8 FEET 481

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR MOHANN DRILLING, INC. LICENSE NUMBER 6394

ADDRESS P.O. BOX 1362, GREAT BEND, Mo. 67530

COMPANY TO PLUG AT: HOUR: 4:10 PM DAY: 29th MONTH: AUG. YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM TERRY WILLIAMSON

(COMPANY NAME) MOHANN DRIG. INC. (PHONE) 316-793-5610

WERE: 8 5/8" - 481' SP. CUL. w/ 225st CNT. 60/140 P.C. - 2% GEL - 3% CA-CL (BY WALLIBURTON)

ORDER 190st 50/150 Pozmix 4% GEL - 3% CA-CL. AND 8 5/8" PLUG.

SPOT WITH DRILL STEM, WITH HEAVY MUD BETWEEN ALL PLUGS

ELV. 1914 - H.A.H. 738 - ARBUCKLE @ 3416 FT

PLUGGING PROPOSAL RECEIVED BY Maryann Schmidt
(TECHNICIAN) DOIC

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE X

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 29th MONTH: AUGUST YEAR: 19 83

ACTUAL PLUGGING REPORT

ORDERED 190st 50/150 Pozmix 4% GEL 3% CA-CL. AND 8 5/8" PLUG

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st Plug @ 3360' w/ 20st CNT., 2nd Plug @ 450' w/ 20st CNT.

3rd Plug @ 570' w/ 80st CNT., 4th Plug @ 240' w/ 40st CNT.

5th Plug ^{SOLID BRIDGE} @ 40' w/ 10st CNT. ^{SHUITS + PLUG}

REMARKS: 10st IN RAT HOLE (CIRCULATE) 10st IN MOUSE HOLE (CIRCULATE)

CEMENTED BY WALLIBURTON CO. INC.

RECEIVED
STATE CORPORATION COMMISSION

AUG 0 8 1983

I ~~DO~~ / DID NOT OBSERVE THIS PLUGGING.

CONSERVATION DIVISION
WICHITA, KANSAS

SIGNED Maryann Schmidt
(TECHNICIAN) DOIC

INVOICED

DATE 8-12-83

INV. NO. 5145-W

FORM CP-213
REV. 6-83
17