

4-061188

5-27

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-24,193 0000

NW SE SE /4 SEC. 14, 16 S, 11 W
990 feet from S section line
990 feet from E section line

Operator license# 100

Lease: Marmie Well # 1

Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #990070-001

County: Barton
Well total depth 3435 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 425 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Quality Well Service License# 31925

Address: 249 E. Beth Dr. - Sterling, Kansas 67579

Company to plug at: Hour: 11:45 A.M. Day: 27 Month: May Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0050

Were: Order 340 sxs 60/40 pozmix - 10% gel and hulls.
Plug with tubing.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour 2:00 P.M., Day: 27, Month: May, Year: 1999

Actual plugging report: 8 5/8" set to 425' w/215 sxs. 5 1/2" to 3435' w/75 sxs.
Perforated casing at 1375' - 700' and 325'. Ran tubing to 2000' and pumped 80 sxs with 300#
hulls. Pulled tubing to 1000' and circulated cement to surface with 100 sxs with 200# hulls.
Pulled tubing and tied onto annulus. Pumped 50 sxs cement. Max. P.S.I. 500#. S.I.P. 300#.
Tied onto production casing and pumped 10 sxs. Max. P.S.I. 500#. S.I.P. 500#.

Remarks: Ted Luebbers-site supervisor. Francis Urban Tank. Beaver Leasing Service.

Condition of casing(in hole): GOOD BAD X
Bottom plug(in place): YES X, CALC , NO
Plugged through TUBING X, CASING
Any plug: YES X NO
Dakota plug: YES X
Elevation: 1831 GL

I did[X] / did not[] observe the plugging.

(V)

Car Marmie
(agent)

STATE CORPORATION COMMISSION Form CP-2/3

JUN 04 1999
06-04-99
CONSERVATION DIVISION
Wichita, Kansas