

3-30-88

4-59

To: 6 070658
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 009-24-305-0000
NE, SW, SE, SEC. 15, T 16 S, R11
990 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9421
Operator: Boger Bros. Drlg. Inc.
Name & Address: P.O. Box 723
Great Bend, Kansas 67530

Lease Name Esfield Well # 1
County Barton 110.73
Well Total Depth 3407 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8" feet 430

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ U&A

Other well as hereinafter indicated _____

Plugging Contractor Boger Bros. Drlg. Inc. License Number 9421
Address Box 723, Great Bend, Kansas 67530

Company to plug at: Hour: 3:30 PM Day: 28 Month: March Year: 19 88

Plugging proposal received from Dale Smith and Ruth

(company name) Boger Bros. Drlg. Inc. (phone) 316-792-8151

were: 8 5/8' 430 FI. Sp. Cur W/175 sks 50/50 Poz. 2% Gel. 3% CaCl. By Halco Arbuckle 3350'
Elev. 1879- Anh. 700, No circulation Problems. Mud condition 50 visconsity- 9.1 weight;
13 water loss, Proposal 195 sks 60/40 poxmix & 4% Gel, 3% CaCl- and 8 5/8" plug, circulate,
spot with drill stem, heavy mud between all plugs, 25 sks @ 3300', 25 sks @ 710'; w/25sks;
80 sks @ 480'; 40 sks @ 240'; hulls and plug @ 40' w/10sks cmt-15 sks Rat Hole (circulate)

Plugging Proposal Received by *MJS* (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 3:30PM Day: 30 Month: Mar Year: 19 88

ACTUAL PLUGGING REPORT Ordered 195 sks 60/40 Poz Mix 4% Gel. 3% CaCl and 8 5/8" plug.

Reconditioned hole, Spotted with Drill Stem, heavy mud between all plugs
1st Plug @ 3300' W/25sks cmt.; 2nd plug @ 710' W/25sks cmt.
3rd plug @ 480' W/80sks cmt.; 4th plug @ 240' W/40sks cmt. ^{5th} Hulls plug @ 40' W/10sks cmt.
15 sks in Rat Hole (circulate) Cemented by Haliburton Cmt.

RECEIVED
STATE CORPORATION COMMISSION
Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
DATE 6-21-88
INV. NO. 20896

JUN - 9 1988
6-9-88 Signed *Mary Schmidt*
CONSERVATION DIVISION
Wichita, Kansas (TECHNICIAN)