

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

15009-20111-0000

NORTH

X			

Locate well correctly on above Section Plat

Barton County, Sec. 10 Twp. 16S Rge. 11 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE SW NW
Lease Owner Allison - Black
Lease Name Redetzke Well No. # 1
Office Address 1415 Wichita Plaza
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed April 29 19 69
Application for plugging approved May 1 19 69
Plugging commenced May 6 19 69
Plugging completed May 10 19 69
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	246	None
				5 1/2	3347	2600

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand to 3100'. Mixed and dumped 5 sacks of cement from 3100' to 3060'. Mixed and pumped 15 sacks of gel. released plug and mixed and pumped 90 sacks of cement, containing 4% gel to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUN 2 1969
CONSERVATION DIVISION
Wichita, Kansas
6-2-69

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Russ Casing Pulling, Inc.
Address P. O. Box 1082, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
1415 Wichita Plaza, Wichita
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of May, 1969

My commission expires Oct. 13, 1972
Lorraine M. Johnson
Lorraine M. Johnson Notary Public.

15-009-20111-0000

DRILLERS LOG

REDETZKE "C" NO. 1

CASING RECORD:	COMPANY:	ALLISON & BLACK	DESCRIPTION:
8-5/8" @ 246'	CONTRACTOR:	SAGE DRILLING CO.	SE SW NW
w/185 sax cement	COMMENCED:	September 24, 1967	Sec. 10-16S-11W
TOTAL DEPTH:	COMPLETED:	October 1, 1967	Barton County, Kansas
3355'			ELEVATION: 1887KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Shale	0	110	
Sand	110	175	
Shale	175	445	
Shale & Sand	445	480	
Shale & Red Bed	480	717	
Anhydrite	717	748	
Red Bed	748	884	
Shale & Shells	884	1375	
Lime & Shale	1375	2130	
Shale & Lime	2130	2745	
Lime & Shale	2745	3128	
Lime	3128	3355	5 1/2" @ 3347' w/100 sax

RECEIVED
STATE CORPORATION COMMISSION
MAY 1 1969
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Lawrence F. Gray
Lawrence F. Gray

Subscribed and sworn to before me this 3rd day of October, 1967.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.