


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Form CP-4
15 009-20191-0000
WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Barton County. Sec. 10 Twp. 16S Rge. (E) 11 (W)
Location as "NE/CNW/SW" or footage from lines NE NW SW
Lease Owner Allison & Black
Lease Name Redetzke A Well No. 1
Office Address 1415 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed 2-7 19 68
Application for plugging filed 2-7 19 68
Application for plugging approved 2-7 19 68
Plugging commenced 6:30 2-7- 19 68
Plugging completed 11:00 2-7 19 68
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan, Russell, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3369' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale		0	241'	8 5/8"	241'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug at 440' with 35 sacks - plug at 220' with 25 sacks
plug & bridge at 40' with 10 sacks - Hole plugged by
Don Truan & Globe Pumping Truck.

RECEIVED
STATE CORPORATION COMMISSION

FEB 14 1968

CONSERVATION DIVISION
Wichita, Kansas

2-14-68

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor B & B Drilling, Inc.
Address 548 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bill Lahar

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lahar
548 Petroleum Building - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of February, 19 68

May 31, 1970

My commission expires

Alma A. Neiser

Notary Public.

B & B DRILLING, INC.

548 Petroleum Building
Wichita, Kansas 67202

February 13, 1968

1500920191-0000

DRILLERS LOG

Re: Redetzke "A" #1
NE NW SW Sec. 10-16S-11W
Barton County, Kansas

COMPANY: Allison & Balck
CONTRACTOR: B & B Drilling, Inc.
TOTAL DEPTH: 3369'
COMMENCED: January 31, 1968
COMPLETED: February 7, 1968

0	42	Soil & Rock
42	185	Rock & Shale
185	208	Sand
208	241	Shale
241	400	Shale & Sand
400	709	Shale
709	744	Anhydrite
744	755	Shale
755	1090	Shale
1090	1485	Shale & Lime
1485	1764	Lime & Shale
1764	1922	Lime & Shale
1922	2240	Shale & Lime
2240	2500	Shale & Lime
2500	2685	Shale & Lime
2685	2848	Lime & Shale
2848	2930	Lime
2930	3063	Lime
3063	3167	Lime
3167	3202	Lime
3202	3248	Lime DST #1
3248	3320	Lime
3320	3356	Lime
3356	3369	Lime
3369		Total Depth : D & A

RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1968
CONSERVATION DIVISION
Wichita, Kansas

We certify the above and foregoing to be true and correct copy of the log on the #1 Redetzke "A" #1, located in Barton County, Kansas.

Bill Labor President

Alma A. Meiss Notary Public
Subscribed and sworn to before me this
13th day of February, 1968
My commission expires May 31, 1970