

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

*Plugged
week of 17th
April*

Form CP-4
Rev. 12-15-80

15-009-20191-0001

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY BARTON SEC. 10 TWP. 16 S RGE. 11 W
Location as in quarters or footage from lines:
1065' from West line & 330' from North Line of SW/4

Lease Owner Pioneer Operations Co., Inc.
Lease Name Redetzke Well No. 2
Office Address P. O. Box 272, Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole): SWD
Date Well Completed Nov. 20, 1979
Application for plugging filed January 12, 1983
Plugging commenced April 14, 1983
Plugging completed April 14, 1983
Reason for abandonment of well or producing formation D & A

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck

Producing formation none Depth to top _____ bottom _____ T.D. 525'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface pipe		0	239'	8"	239'	none
Cedar Hills		200'	525'	5 1/2"	525'	none

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

The top perforations at 219' were squeezed with 500 sacks of common cement
followed with rubber plug at 200', 500 pounds of pressure was used. Ran tubing
to 200' and circulated cement to the surface with 20 sacks of cement; pumped 5
sacks of cement in 8 5/8" surface pipe with 700 pounds pressure.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Smoky Hill Well Service, Inc.

STATE OF Kansas COUNTY OF Russell, ss.

Ronald E. Smith (employee of owner) or (~~owner or operator~~) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Ronald E. Smith
P. O. Box 272, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of April, 1983

Clifford R. Holland
Notary Public.

My Commission expires: November 12, 1984

RECEIVED
STATE CORPORATION COMMISSION

APR 21 1983
4-21-83
CONSERVATION DIVISION
Wichita, Kansas

B & B DRILLING, INC.

548 Petroleum Building
Wichita, Kansas 67202

February 13, 1968

DRILLERS LOG

Re: Redetzke "A" #1
NE NW SW Sec. 10-16S-11W
Darton County, Kansas

COMPANY: Allison & Balch
CONTRACTOR: B & B Drilling, Inc.
TOTAL DEPTH: 3369'
COMMENCED: January 31, 1968
COMPLETED: February 7, 1968

0	42	Soil & Rock
42	185	Rock & Shale
185	208	Sand
208	241	Shale
241	400	Shale & Sand
400	709	Shale
709	744	Anhydrite
744	755	Shale
755	1090	Shale
1090	1405	Shale & Lime
1485	1764	Lime & Shale
1764	1922	Lime & Shale
1922	2240	Shale & Lime
2240	2500	Shale & Lime
2500	2685	Shale & Lime
2685	2848	Lime & Shale
2848	2930	Lime
2930	3063	Lime
3063	3167	Lime
3167	3202	Lime
3202	3248	Lime DST #1
3248	3320	Lime
3320	3356	Lime
3356	3369	Lime
3369		Total Depth D & A

RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1968
CONSERVATION DIVISION
Wichita, Kansas

H-29-83

We certify the above and foregoing to be true and correct copy of the log on the #1 Redetzke "A" #1, located in Barton County, Kansas.

Bill Lohar President

Clara G. Mission Notary Public
Subscribed and sworn to before me this
13th day of February, 1968
My commission expires May 31, 1970