

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

15-009-22322-0000  
 Form CP-4  
 Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Barton SEC. 10 TWP. 16s RGE. 11w E/W  
 Location as in quarters or footage from lines:  
 SW SE SE


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Brougner Oil Inc,  
 Lease Name Redetzke #1 Well No. \_\_\_\_\_  
 Office Address 614 Patton Rd, P.O. Drawer 1367, Great Bend, Ks.  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 1/28/83  
 Plugging completed 3/18/83  
 Reason for abandonment of well or producing formation \_\_\_\_\_

\_\_\_\_\_ Depleted  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3330'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	296'	none
				5 1/2"	3324'	2471'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Plugged bottom with 5 sacks cement, sand to 3100' & 5 sacks cement.  
Shot pipe at 2712', 2623', & 2505'. Pulled total of 59 joints. Plugged  
well with 4 hulls, 12 gel, 65 cement, 3 gel, 1 hull, released plug &  
displaced with 100 sacks cement, 50/50 pos. 4% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347, Chase, Ks. 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of March, 1983

My Commission expires:



Irene Hoover RECEIVED  
 STATE CORPORATION COMMISSION

MAR 21 1983  
 3-21-83  
 CONSERVATION DIVISION  
 Wichita, Kansas