

15209-00307-0080

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Barton County. Sec. 15 Twp. 16S Rge. 11 (E) (W)

Location as "NE/CNW/SW" or footage from lines 330 FNL 330 FWL

Lease Owner Grant Oil Company

Lease Name Redetzke "C" Well No. 1

Office Address 518 W-K-H Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 30, 1956 19 56

Application for plugging filed July 23 19 56

Application for plugging approved July 25 19 56

Plugging commenced August 11 19 56

Plugging completed August 13 19 56

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production Never Produced 19     

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage

Producing formation Arbuckle Depth to top 3344 Bottom 3367 Total Depth of Well 3369 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	water	0	186	8 5/8	186	none
Arbuckle	dry	0	3368	5 1/2	3368	2730

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fill hole with sand to 3335' Dumped 5 sacks cement, pulled pipe to 900' - dumped 20 sacks cement - Pull pipe to 320' - Pump in 75 sacks cement - mud hole to 26' - Dump 5 sacks cement to top.

9-29-56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Arnett Casing Pulling Co. License # 265

Address Hoisington, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

W. A. Grant (~~employee of owner~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. (So help me God.)

(Signature) W. A. Grant

518 W-K-H Building, Wichita 2, Ks.

(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of September, 19 56

NOTARY PUBLIC

My Commission Expires March 1, 1960

My commission expires \_\_\_\_\_

Martha Lasky  
Notary Public

24-2675-8 2-52-20M

PLUGGING  
FILE SEC. 15 T. 16 R. 11W  
BOOK PAGE 83 LINE 24

15-009-00307-0000

REDETZKE "C" NO. 1

Location: NW/4 NW/4 NE/4 Sec. 15-16S-11W, Date Spudded: 6-19-56  
 Barton County, Kansas

Operator: Grant Oil Company Rotary Completion: 6-30-56

Contractor: Walters Drilling Co. Elevation: 1881 Gr  
 1883 DF  
 1886 KB

Surface Casing: 8 5/8" set at 186' with  
 175 sacks cement and  
 2 Gal. Chloride

Oil String: 5 1/2" set at 3368' with  
 100 sacks cement

L O G

(Figures indicate bottom of formation)

Surface	0 to 186
Shale, shells and sand	690
Shale and shells	716
Anhydrite	740'
Shale and shells	1260
Lime and shale	2890
Lime	2934
Lime and shale	3115
Lime	3296
Lime and shale	3354
Lime	3369
Rotary Total Depth	3369

The undersigned, Robert F. Walters, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

By

Robert F. Walters

Subscribed and sworn to before me  
this 5th day of July, 1956

Pauline R. Rudolph  
Notary Public

My commission expires:  
March 10, 1960

PLUGGING  
 FILE SEC. 15 T. 16 R. 11W  
 BOOK PAGE 83 LINE 24