


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 15 Twp. 16 Rge. (E) 11 (W)
Location as "NE/CNW/SW" or footage from lines NE - SW - NE
Lease Owner Wilkinson Drilling Company
Lease Name Redetske Well No. 1
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced June 24 1958
Plugging completed June 28 1958
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	405	None
				5 1/2	3359	2723.03

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3350' - dumped 5 sks cement - mudded to 405' -
set 10' rock bridge - dumped 20 sks cement - mudded hole to 40' - set 10'
rock bridge - dumped 10 sks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Company License # 236
Address P. O. Box 569 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgewick, ss.
WALTER M. WILKINSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter M. Wilkinson
1121 UNION NAT'L. BLDG. - WICHITA 2,
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of July, 1958

Carolyn T. Moore
Notary Public.

My commission expires Jan. 2, 1961

RECEIVED
STATE CORPORATION COMMISSION
JUL 25 1958
7-25-58
CONSERVATION DIVISION

PLUGGING
FILE SEC 15 T. 16 R. 11W
BOOK PAGE 114 LINE 21

WILKINSON DRILLING INCORPORATED
1111 UNION NATIONAL BUILDING
WICHITA 2, KANSAS

15-009 074000000

ANTON REDETZKE #1

Company	- Wilkinson Drilling, Inc.	Location:	NE SW NE, Sec. 15-16S-11W, Barton County, Kansas.
Contractor	- Company Tools	Elevation:	1888 DF, 1890 RB
Commenced	- 3-7-57	Casing:	405' - 8 5/8" cemented W/285 Sk. Common Cement - 5 Sk. gel, 5 Sk. C.C.
Completed	- 3-16-57		
Total Depth	- 3365'		

FIGURES INDICATE BOTTOMS OF FORMATION:

Depth	Formation
0 - 405	Sand & Shale
405 - 615	Shale & Shells
615 - 725	Red Beds, Shale & Shells
725 - 760	Anhydrite
760 - 1425	Shale & Shells
1425 - 2980	Shale & Lime
2980 - 3322	Lime
3322 - 3343	Conglomerate
3343 - 3365	Dolomite (Arbuckle)
3365 - T. D.	

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1964

CONSERVATION DIVISION
Wichita, Kansas

We hereby certify the above and foregoing to be a true and correct copy of the log on the #1 Anton Redetzke, located in the NE SW NE, Section 15-16S-11W, Barton County, Kansas.

WILKINSON DRILLING, INC.

Walter M. Wilkinson
Walter M. Wilkinson

Subscribed and sworn to before me this 25th day of March, 1957.

Carol K. Moore
Notary Public

My commission expires January 2, 1961.