

15009-20743-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Barton SEC. 15 TWP. 16 RGE. 11W E/W
 Location as in quarters or footage from lines:
SE/4 NW/4 SE/4

Lease Owner Southern States Oil Company
 Lease Name Esfeld #1 Well No. _____
 Office Address P.O. Box 1365 Great Bend, Kansas 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 9-22-82
 Plugging completed 9-29-82
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck
 Producing formation _____ Depth to top _____ bottom T.D. 3359'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	194'	none
				5-1/2"	3358'	2365'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 3100' and ran 5 sacks cement. Shot casing @2617', 2500', 2385' and pulled a total of 75 joints of 5-1/2" casing. Plugged well with 4 sacks hulls, 12 gel, 70 cement, 3 gel, 1 hull, released plug and displaced with 70 sacks cement, 50/50 pos, 4% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
 Box 347 Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 1982

My Commission expires:



Irene Hoover
 RECEIVED Public
 STATE CORPORATION COMMISSION

SEP 30 1982
 9-30-82
 CONSERVATION DIVISION
 Wichita, Kansas

15-009 20743-00-00

W E L L L O G

DATE COMMENCED: August 10, 1973
DATE COMPLETED: August 18, 1973

Icer Addis
ESFELD #1
SE/4 NW/4 SE/4
Sec. 15-T16S-11W
Barton County, Kansas

ELEVATION: 1891 K.B.

0	-	65'	Post Rock
65	-	182'	Shale
182	-	510'	Clay
510	-	709'	Red Bed
709	-	736'	Anhydrite
736	-	859'	Red Bed
859	-	1435'	Shale
1435	-	1770'	Lime & Shale
1770	-	2913'	Shale & Lime
2913	-	2916'	Shale
2916	-	2933'	Lime & Shale
2933	-	2943'	Lime
2943	-	3007'	Shale
3007	-	3022'	Br. Lime
3022	-	3292'	Lime
3292	-	3319'	Shale & Lime
3319	-	3331'	Shale, Lime, Chert
3331	-	3354'	Congl. Sand
3354	-	3359'	Dolomite
		3359'	RTD

FORMATION DATA

ANHYDRITE	709
HEEBNER	2913
TORONTO	2933
DOUGLAS	2943
BR. LIME	3007
KANSAS CITY	3022
BASE K.C.	3292
CONGLOMERATE	3319
CONGL. SAND	3331
ARBUCKLE	3354
RTD	3359

SURFACE PIPE: Set used 28#, 8-5/8" pipe at 194' with 150 sacks common cement, 2% Gel, 3% Ca.C.

PRODUCTION CASING: Set used 5 1/2" casing, 14 1/2 & 15#, at 3358' with 125 sacks 60/40 pozmix, salt sat. with 15 bbls. salt flush ahead of cement.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 22nd day of August 1973.

Notary Public

My Comm. Expires:
April 11, 1974

RECEIVED
STATE CORPORATION COMMISSION

AUG 02 1973

CONSERVATION DIVISION
Wichita, Kansas