

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15009-20785-0000

LEASE NAME Sauber

WELL NUMBER #1

SPOT LOCATION NW SW NE

SEC. 15 TWP. 16 SRGE. 11W (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 3-19-86

Plugging Completed 3-21-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Lasmo Energy Corporation

ADDRESS P.O. Box 1365 Great Bend, Kansas 67530

PHONE # (316) 792-2585 OPERATORS LICENSE NO. 4678

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3362'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	208'	none
				4-1/2"	3357'	1011'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Sanded off bottom to 3100' and 4 sacks cement. Shot casing @2023', 1011', pulled a total of 34 joints (1011') of 4-1/2" casing. Plugged surface with 5 hulls and 55 sacks cement (econalite) 100# Max. Shut in 650# Plugging Complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 25 day of March, 1986

My Commission expires: _____



STATE CORPORATION COMMISSION
Notary Public

MAR 27 1986
3-27-86
CONSERVATION DIVISION