

15 009-01223-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barton County, Sec. 16 Twp. 16<sup>S</sup> Rge. (E) 11 (W)

Location as "NE/CNW&SW¼" or footage from lines NW NE SE

Lease Owner Wilkinson Drilling, Inc.

Lease Name Esfeld Well No. #1

Office Address 805 Union Center, Wichita 2, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12/13 1961

Application for plugging filed 12/13/61 1961

Application for plugging approved 12/13 1961


Plugging commenced 12/13 1961

Plugging completed 12/13 1961

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Donald Truan, Russell, Kansas.

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

First plug set @250' W/20 sacks cement, ¼ sack Hulls.  
Second plug set @40' W/10 sacks cement, ¼ sack Hulls,  
Plug down @8:30 PM, 12/13/61

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 23 1962  
1-23-62  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Wilkinson Drilling, Inc.  
Address 805 Union Center, Wichita 2, Kansas.

STATE OF Kansas. COUNTY OF Sedgwick, ss.  
Walter M. Wilkinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter M. Wilkinson  
805 Union Center, Wichita 2, Kansas.  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of December, 19 61

My commission expires January 2, 1965  
Carolyn K. Iverson  
Carolyn K. Iverson Notary Public.



January 17, 1962

Wilkinson Drilling, Inc.  
Esfeld #1

NW NE SE, Sec. 16-16<sup>S</sup>-11<sup>W</sup>,  
Barton County, Kansas.

Contractor: Wilkinson Drilling, Inc.  
Commenced: December 4, 1961  
Completed: December 13, 1961  
Elevation: 1882 Kelly Bushing  
Casing: 8 5/8" @255' W/170 sacks cement  
Total Depth: 3353'

FIGURES INDICATE BOTTOMS OF FORMATION

<u>DEPTH</u>	<u>FORMATION</u>
0 - 960	Shale & Shells
960 - 990	ANHYDRITE
990 - 1410	Shale & Shells
1410 - 1605	Lime
1605 - 1780	Shale & Lime
1780 - 2922	Lime & Shale
2922 - 2927	HEEBNER Shale
2927 - 2953	Lime & Shale
2953 - 3018	Shale & Silty Shale
3018 - 3325	Lime & Shale Streaks
3325 - 3341	Varicolored Shale & Chert
3341 - 3343	Weathered ARBUCKLE
3343 - 3353	ARBUCKLE Dolomite

RECEIVED  
STATE CORPORATION COMMISSION

JAN 23 1962

CONSERVATION DIVISION  
Wichita, Kansas

We hereby certify the above and foregoing to be a true and correct copy of the driller's log on the Esfeld #1, located NW NE SE of Section 16-16<sup>S</sup>-11<sup>W</sup>, Barton County, Kansas.

WILKINSON DRILLING, INC.

Walter M. Wilkinson  
Walter M. Wilkinson

Subscribed and sworn to before me this 17th day of January, 1962.

Carolyn K. Iverson  
Carolyn K. Iverson-Notary Public

My commission expires: January 2, 1965.