

15009-03025-0001


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely!  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barton County, Sec. 16 Twp. 16 Rge. 11 (E) (W) X  
Location as "NE/CNW/SW" or footage from lines C, SW NW SW SW  
Lease Owner Graham-Michaelis Corp.  
Lease Name Redetzke C Well No. #1 SWD  
Office Address 211 N. Broadway Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 5-24-73 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 5-25-73 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3337' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3329'	Plug only
				8 5/8"	540'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Squeezed 5 1/2" casing by circulating 20 sacks gel. 2 sacks hulls and displaced with 75 sacks cement. Between 8 5/8" and 5 1/2" casing displaced with 75 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 25 1973  
5-25-73  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Southwest Casing Pulling Co.  
Address Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.  
Box 364 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of May, 19 73

My commission expires



Sidney D. Miller  
Notary Public.

COMPANY G-M-R Oil Co.

FARM Redetzke "C" No. 1


SEC. 16 T. 16 R. 11W

LOC. NW-SW-SW

C 5/4 5/4 5/4  
NW

COUNTY Barton

KANSAS



TOTAL DEPTH 3339'

COMM. 3-26-51

COMP. 4-5-51

SHOT OR TREATED

CONTRACTOR J. W. Braden Drlg. Co.

ISSUED 6-9-51

CASINO

8 5/8" 540' w/ 300 sh  
5 1/2" 3329' w/ 85 sh

ELEVATION 1886

PRODUCTION Pot 25 bbls.

FIGURES INDICATE BOTTOM OF FORMATIONS

shale & shells	245
shale & shells	395
sand	530
red bed	540
red bed	732
anhydrite	767
shale & shells	770
shale & shells	1430
lime	2075
shale & lime	2205
broken lime	2400
lime	2505
shale & lime	2630
lime	2807
lime & shale	2885
lime	2950
lime & sand	3045
lime	3285
lime, shale & conglomerate	3339
Total depth	

Scout Tops:	
Heebner	2922
Toronto	2941
Douglas shale	2953
Sand	2989
Brown Lime	3018
Lansing, K. C.	3040
Conglomerate	3315
Conglomerate sand	3321

3043  
1583  
-1150

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 15 1973  
CONSERVATION DIVISION  
Wichita, Kansas

REDETZKE 61

Section 16, Township 16, Range 11W

Barton County, Kansas

Drilling Contractor - J. W. Braden Drilling Company

Operator - G-M-R Oil Company

Date Started - March 26, 1951

Date Finished - April 5, 1951

Shale and Shells	0 to 245
Shale and Shells	245 to 395
Sand	395 to 530
Red Bed	530 to 540
Red Bed	540 to 732
Anahydrate	732 to 767
Shale and Shells	767 to 770
Shale and Shells	770 to 1430
Lime	1430 to 1650
Lime	1650 to 1835
Lime	1835 to 1945
Lime	1945 to 2075
Shale and Lime	2075 to 2205
Broken Lime	2205 to 2400
Lime	2400 to 2505
Shale and Lime	2505 to 2630
Lime	2630 to 2730
Lime	2730 to 2807
Lime and Shale	2807 to 2885
Lime	2885 to 2950
Lime and Sand	2950 to 3045
Lime	3045 to 3065
Lime	3065 to 3120
Lime	3120 to 3180
Lime	3180 to 3225
Lime	3225 to 3285
Lime Shale and Cong.	3285 to 3329 Total Depth

RECEIVED  
STATE CORPORATION COMMISSION

MAY 15 1973

CONSERVATION DIVISION  
Wichita, Kansas

Set 540' of 8-5/8" casing

Run 3329' of 5 1/2" casing.

STATE OF KANSAS

COUNTY OF RENO

} SS:  
}

I hereby certify that the above information is true and correct  
to the best of my knowledge.

J. W. Braden  
Subscribed and sworn to before me this third day of May, 1951

M. L. Bowman  
Notary Public

My Commission Expires:

March 21, 1953

GMR  
File Copy