

OR  
FORMATION PLUGGING RECORD


Strike out upper line when reporting plugging of formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Barlow County, Sec. 16 Twp. 16 Rge. 11 (E) N (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. 100 200 300  
Lease Owner. Harba Drilling Company  
Lease Name. Joseph H. Lawick Well No. 1  
Office Address. 1019 Central Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed. August 9, 1945 19  
Application for plugging filed. September 14, 1945  
Application for plugging approved. September 14, 1945  
Plugging commenced. September 14, 1945  
Plugging completed. September 20, 1945  
Reason for abandonment of well or producing formation. Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production. 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, H. W. Kerr

Name of Conservation Agent who supervised plugging of this well. H. W. Kerr  
Producing formation. Depth to top. Bottom. Total Depth of Well. 5237' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand-shale & shells	water	0	545	10 3/4"	354'	None
		0	5237'	5 1/2"	5237'	1544' 6"
				3 1/2"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.  
Hole filled with heavy mud and 5 sacks of cement run @ 5237' to 5245'  
Pine shot loose and pulled 1644' 6" of pipe. Hole mudded to 250' and permanent plug placed at 250' and cemented with 15 sacks of cement. Heavy mud used to 25' and plug cemented with 10 sacks of cement from 25' to bottom of collar.

PLUGGING  
FILE 16 16 R 11W  
BOOK PAGE 28 LINE 4



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Harba Drilling Company,  
Address. 1019 Central Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF \_\_\_\_\_, ss.  
Jim Adkins (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Adkins  
1902- 17th St., Great Bend, Kansas.  
(Address)


SUBSCRIBED AND SWORN to before me this 31st day of December, 1945

My commission expires April 7, 1947  
Margaret O. Reilly  
Notary Public

LAUDICK #1  
NW SE SW 16-16-11W, Barton County, Kans.

Rigging up 7-7-45  
Tearing down 8-9-45  
Ran 120' 10 3/4" Spiral Weld Pipe; 354' 10 3/4" surface casing

FORMATION	FROM	TO	REMARKS
Surface rock	0	55	
Sand	55	75	
Shale & Shells	75	155	
Shale & Shells	155	325	
Sand	325	345	
Red Bed	345	360	
Shale & Shells	360	670	
Lime	670	700	
Anhydrite	700	720	
Red Bed & Shale	720	800	
Shale & Shells	800	1145	
Salt & Shale	1145	1210	
Shale & Shells	1210	1375	
Shale	1375	1525	
Lime & Sand	1525	1545	
Sand	1545	1550	
Shale	1550	1625	
Shale & Lime	1625	1700	
Lime	1700	1830	
Shale & Lime	1830	1915	
Shale	1915	1930	
Lime & Shells	1930	2050	
Lime	2050	2135	
Shale & Lime	2135	2205	
Lime, Shale & Shells	2205	2295	
Shale	2295	2300	
Shale & Lime Shells	2300	2375	
Shale & Lime	2375	2445	
Shale & Lime	2445	2505	
Shale & Shells	2505	2605	
Lime	2605	2615	
Shale & Lime	2615	2670	
Lime	2670	2710	
Lime & Shale	2710	2760	
Lime	2760	2980	
K. C. Lime	2980	3025	
Lime	3025	3295	
Conglomerate	3295	3346	
Arb. Lime	3346	3353	T.D.



I, W. A. Grant, do solemnly swear that the above log is true and correct to the best of my knowledge.

*W. A. Grant*

Subscribed and sworn to before me and in my presence this 30<sup>th</sup> day of August, 1945.

*Margaret O'Reilly*  
Notary Public

My commission expires 4-7-47

PLUGGING  
FILE NO. 16-16-R-11W  
BOOK PAGE 28 LINE 4