


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec 16 Twp. 16S Rge. 11 (W)
Location as "NE/CNW/SW" or footage from lines SE NW SE
Lease Owner H-30, Inc., et al
Lease Name Esfeld Well No. 4
Office Address 200 N. Main, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 26 19 68
Application for plugging filed Verbal Authority 19
Application for plugging approved Verbal Authority 19
Plugging commenced March 26 19 68
Plugging completed March 26 19 68
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	282'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 3,383 feet (rotary total depth) to 480 feet. Set bottom plug at 480 feet and cemented with 30 sacks cement by Globe Oilwell Cementing, Inc. Pump Truck. Filled hole with heavy rotary mud to 270 feet. Set plug at 270 feet and cemented with 25 sacks cement by Globe Pump Truck. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented to cellar with 10 sacks cement by Globe Pump Truck, 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
APR 2 1968
CONSERVATION DIVISION
Wichita, Kansas
4-2-68

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, Inc.
Address 200 N. Main St., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B. Romer
200 N. Main St., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of April, 1968

My commission expires April 21, 1971

Martha Hartpence
(Martha Hartpence) Notary Public.

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15-009-20208-0000

COMPANY H-30, INC., Et Al

SEC. 16 T. 16S R. 11W

FARM Esfeld NO. 4


LOC. SE NW SE

TOTAL DEPTH 3,383'
 COMM. March 18, 1968
 SHOT OR TREATED
 CONTRACTOR H-30, Inc.
 ISSUED

COMP. March 26, 1968

COUNTY Barton

KANSAS



CASING

20	10		
15	8-5/8"	282' cemented w/135 sx cement	ELEVATION 1901 KB
12	6		
13	5		

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

SAMPLE TOPS

Surface Shale & Post Rock	48	Topeka	2643 - 742
Clay & Shale	282	Heebner	2939 - 1038
Shale & Shells	470	Toronto	2956 - 1055
Sand & Iron	516	Douglas	2970 - 1069
Red Bed	744	Brown Lime	3032 - 1131
Anhydrite	771	Lansing K.C.	3051 - 1150
Shale	1455	Base K.C.	3311 - 1410
Salt	1485	Arbuckle	3371 - 1470
Shale & Lime	1715	Rotary T.D.	3383 - 1482
Lime	1832		
Flint	2018		
Shale & Lime	2540		
Lime & Shale	2644		
Lime	2937		
Shale	2955		
Lime	3340		
Conglomerate	3370		
Lime	3383		
Rotary Total Depth	3383		

RECEIVED
 STATE CORPORATION COMMISSION
 APR 2 1968
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer
 Arlo B. Romer

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 1st day of April, 1968.

Martha Hartpence
 Martha Hartpence - Notary Public

My Commission Expires:

April 21, 1971