

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-62-3-117

API NUMBER 15-093-00374-00-00

LEASE NAME STUART

WELL NUMBER #1

2540 Ft. from S Section Line

2540 Ft. from E Section Line

SEC. 26 TWP. 24S RGE. 38 (E) or (W)

COUNTY KEARNY

Date Well Completed Oct. 1948

Plugging Commenced 8/7/2001

Plugging Completed 8/8/2001

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR OSBORN HEIRS COMPANY

ADDRESS P.O. Box 17968, San Antonio, Texas 78217

PHONE (210) 826-0700 OPERATORS LICENSE NO. 5249

Character of Well GAS

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by DISTRICT # 1 OFFICE (KCC District Agent's Name).

Is ACO-1 filed? unknown If not, is well log attached? YES

Producing Formation Chase Depth to Top 2514 ft. Bottom 2705 ft. T.D. 2705 ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE 2514-2705	GAS & WATER	0	705	8 5/8	705	0
		0	2684	5 1/2	2684	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
**SET PLUGS AS FOLLOWS:**

PLUG No. 1 - SET CTRP at 2490 ft. with 3 sacks cement on top  
Pump 46 barrels mud. Perforated 5 1/2" casing at 735 ft.  
PLUG No. 2 - Pump 145 sack cement slurry through perfs at 735 ft.  
Circulated cement to surface in 8 5/8" casing.

Name of Plugging Contractor Superior Servicing Inc. License No. 32297

Address P.O. Box 772, Liberal, Kansas 67905

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OSBORN HEIRS COMPANY

STATE OF TEXAS COUNTY OF BEXAR, ss.

Nancy A. FitzSimon, Engineering Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Nancy A. FitzSimon  
Nancy A. FitzSimon, Engineering Manager

(Address) \_\_\_\_\_

RECEIVED

JAN 22 2002

SUBSCRIBED AND SWORN TO before me this 18th day of January, 2002

KCC WICHITA

My Commission Expires: \_\_\_\_\_

Mary J. Castoreno  
Notary Public

1-22-02



Form CP-4  
Revised 05-88

OR