

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-093-20627-0000

LEASE NAME Wheeler Gas Unit /B/

WELL NUMBER 2

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1320 Ft. from S Section Line

1960 Ft. from E Section Line

LEASE OPERATOR Amoco Production Company

SEC. 24 TWP. 24 SRGE. 37 (E) or (W)

ADDRESS PO Box 800 Room 924 Denver, CO 80201

COUNTY Kearny

PHONE# (303) 830-5323 OPERATORS LICENSE NO. 5952

Date Well Completed 8-2-79

Character of Well Gas

Plugging Commenced 11-13-95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-13-95

The plugging proposal was approved on September 21, 1995 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Council Grove Depth to Top 2750' Bottom 2842' T.D. 3009'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface			8 5/8"	620'	
	Production			5 1/2"	3009'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.  
See Attached.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. KANSAS CORPORATION COMMISSION

Address \_\_\_\_\_

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Amoco Production Company

DEC 18 1995

STATE OF Colorado COUNTY OF Denver, ss. CONSERVATION DIVISION WICHITA, KS

Susan R. Potts (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Susan R. Potts

(Address) PO, Box 800 Room 924 Denver, CO 80201

SUBSCRIBED AND SWORN TO before me this 15<sup>th</sup> day of December, 19 95

My Commission Expires: January 4 1997 Notary Public

1070 BROADWAY  
DENVER, CO 80201  
Form CP-4  
Revised 05-88

Date: 9/21/1995

**Type of Operation: Plug & Abandonment****Lease and Well Number:** Wheeler Gas Unit B No. 2**Field:** Hugoton**Formation:** Council Grove**Location:** Sec 24- T24S - R37W**TD:** 3009' **PBTD:** 3001'**Surface Csg:** 8 5/8" 24 ppf set @ 620', cmt w/ 250 sx**Production Csg:** 5 1/2" 14 ppf set @ 3009', cmt w/ 600 sx**Purpose:** TO PxA the Subject Well**Procedure:**

- 1- MIRU. POOH w/ tbg & rods.
- 2- Set a cement plug to the surface w/ 470 sx of 65/35 POZ, 14.4 ppg, Class 'C' cement.  
Add 2 sx of cotton seed hulls to the first 10 sx of cement.
- 3- Check the backside and have 50 additional sx of cement on location.
- 4- Cut off csg 3' below the ground and weld on steel cap w/ lease identification.
- 5- Restore the location.

**Note:** Please contact the KCC 5 days prior to the scheduled date.

Procedure reviewed w/ KCC representative Steve Middleton on 9/21/95.

Prepared By: Sonia K. Vahedian  
Petroleum Engineer**RECEIVED**  
KANSAS CORPORATION COMMISSION

DEC 18 1995

CONSERVATION DIVISION  
WICHITA, KS