


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Kearney County, Sec. 22 Twp. 24 Rge. 38 (E) # (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SE SE NW
Lease Owner Sooner Pipe & Supply Corporation
Lease Name Iman Wiatt Well No. 1
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 1-8-66 19
Plugging completed 1-10-66 19
Reason for abandonment of well or producing formation Depleted
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Depth to top Bottom Total Depth of Well 2715 Feet
Show depth and thickness of all water, oil and gas formations. PBDT 2620'

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Hemington-Krider		2536	2551	8 5/8"	745'	None
				5 1/2"	2676'	788'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled casing from 2620' to 2580' with sand. Dumped 20 sacks of cement from 2580' to 2455', pulled 5 1/2" casing and dumped 35 sacks of cement from 800' to 700'. Mudded hole to 45' and ran 15 sacks of cement to base of cellar. Welded plate on 8 5/8" casing

PLUGGING COMPLETE

RECEIVED
STATE CORPORATION COMMISSION
DEC 24 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Paul J. Knight (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul Knight

(Address) Responder

Subscribed and sworn to before me this 20th day of December 1968
Margaret Melcher
Notary Public.

My commission expires 2-15-71

FORMATION RECORD

15-093-00370-0000

Nature of Strata	Color	Top	Bottom	Straight Hole tests	Remarks
Sand & clay		0	193		
Sand		193	285	OK	
Sand, shale & clay		285	557	OK	
Shale		557	705		
Red bed		705	750		
Red bed, sand & gyp		750	1280	OK	
Salt		1280	1370		
Shale & sand		1370	1710	OK	
Shale		1710	1990		
Shale & anhydrite		1990	2210	OK	
Shale		2210	2392		
Anhydrite	White	2392	2455		
Dolomite & shale		2455	2526	OK	
Lime		2526	2531		
Shale	Red	2531	2533		
Lime		2533	2551		
Shale & lime		2551	2578		
Lime		2578	2607		
Shale & Lime		2607	2638		

RECEIVED
STATE CORPORATION COMMISSION

NOV 1 1965

CONSERVATION DIVISION
Wichita, Kansas

Iman Watt #1

Sec. 22-24-38^W

be. be. nu. Kearney Co.

