

STATE OF KANSAS
CORPORATION COMMISSION
100 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-093-21191-0000

LEASE NAME HILLYARD FARMS

WELL NUMBER 1

2310 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 14 TWP. 24S RGE. 37W (E) or (W)

COUNTY Kearny

Date Well Completed March 1992

Plugging Commenced 6/25/98

Plugging Completed 6/25/98

RECEIVED
7-2-98
NOV 2 3 1998
OFFICE: Fill out completely
and return to Cons. Div.
office within 30 days.
CONSERVATION DIVISION
Wichita, Kansas

LEASE OPERATOR AMOCO PRODUCTION COMPANY

ADDRESS P. O. Box 800 Room 720C

PHONE# (303) 830-4224 OPERATORS LICENSE NO. 5952

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 14, 1998 (date)

by Gary Winters (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? n/a

Producing Formation Lansing "G" Depth to Top 3986' Bottom 4018' T.O. 5190'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface			8-5/8"	1750'	-0-
	Production			5-1/2"	4244'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

MIRU Hall. Pump 25 sacks of cement from 3630-4006'. Pump 40 barrels mud from 1900-3630'. Pump 155 sacks of cement from 4-1900'. Pump 35 sacks between 8-5/8" casing and 5-1/2" casing. Cut off and cap casing 4' below ground. Job witnessed by Gary Winters of KCC.
(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Halliburton Energy Services License No. _____

Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Amoco Production Company

STATE OF Colorado COUNTY OF Denver, ss.

Debra L Kerps (Employee of Operator) or (Operator) of above-described well, being duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) [Signature]

(Address) P.O.Box 800 Denver CO 80201

SUBSCRIBED AND SWORN TO before me this 16th day of July, 19 98

Virginia J. Williams
Notary Public

My Commission Expires: 11-14-1998