


15-095-01811-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec. 12 Twp. 30 Rge. 8 (X) W (W)
Location as "NE/CNW/SW" or footage from lines NW NW NE
Lease Owner Petroleum, Inc.
Lease Name Young Well No. 1
Office Address Route 2, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed July 29 19 58
Application for plugging filed July 29 19 58
Application for plugging approved July 30 19 58
Plugging commenced Sept. 1 19 58
Plugging completed Sept. 4 19 58
Reason for abandonment of well or producing formation No producible zones

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation ----- Depth to top --- Bottom --- Total Depth of Well 4225 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8. 5/8"	257'	None
				4 1/2"	4221'	3250'
Mississippi	Water & little gas	4132'	4142'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

(Plugged back to 4189')

Filled hole with crushed rock from 4189' to 4110'. Placed 5 sacks cement on top of rock. Mud up to 250' and built solid rock bridge. Placed 25 sacks cement on top of rock bridge and mudded up to 35'. Filled hole to base of well cellar with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Plugging Service
Address 102 W. 18th Street, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Don Searle (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle

Route 2, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of September, 19 58

My commission expires July 11, 1960

Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC. 12 T. 30 R. 20W
BOOK PAGE 119 LINE 8

SEP 8 1958
9-8-58
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

COMPANY Petroleum, Inc.

SEC. 12 T. 30S R. 8W

FARM YOUNG

NO. 1

LOC. NW NW NE


TOTAL DEPTH 4225'

COUNTY Kingman

COMM. July 2, 1958

COMP. July 10, 1958

CONTRACTOR Garvey Drilling Company



CASING 8-5/8" @ 257' w/175 sax
4-1/2" @ 4221' w/125 sax

ELEVATION 1507' DF

PRODUCTION Plugged & Abandoned

FIGURES INDICATE BOTTOM OF FORMATIONS

45 Clay & Red Rock
160 Red Rock w/streaks Sand
257 Red Shale w/Gyp Streaks
350 Shale
1165 Shale w/sand streaks
1200 Lime
1300 Shale & Shells
1508 Shale, Shells & Lime
1685 Lime & Shale
1825 Lime
1950 Shale & Lime
2125 Lime & Shale
2535 Shale & Lime
3025 Shale & Shells
3140 Shale w/Lime Streaks
3305 Shale & Lime
3440 Lime & Shale
3655 Lime
3705 Lime & Shale
3752 Cherty Lime
3865 Lime
3953 Lime & Shale
3989 Lime
4032 Shale & Lime
4083 Lime & Shale
4125 Shale w/Lime streaks
4145 Chert (Miss.)
4198 Cherty Lime
4225 Lime

RTD 4225'

RECEIVED
STATE CORPORATION COMMISSION

SEP 8 1958

CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS

County of BARTON

ss:

PLUGGING

FILE SEC. 12 T. 30 R. 8W
BOOK PAGE 119 LINE 8

I, Verne A. Morris

of Garvey Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Young #1 well

Subscribed and sworn to before me this 25th day of August 19 58

My Commission Expires: July 11, 1966

John T. Brown
NOTARY PUBLIC