


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-009-19239-0000

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 10 Twp. 16 S Rge. (E) 11 (W)
Location as "NE/CNW*SW*" or footage from lines App. NE/4 NW/4 NW/4
Lease Owner Messman-Rinehart Oil Company
Lease Name Redetzke "D" Well No. 1
Office Address 1432 Wichita Plaza Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 17 1963
Application for plugging filed August 17 1963
Application for plugging approved August 17 1963
Plugging commenced August 18 1963
Plugging completed: August 18 1963
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker, Victoria, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3354 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	296'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 290 ft. w/1/4 sk. hulls and 23 sx. cement. Fill hole to 40 ft., set wood plug w/1/4 sk. hulls and 10 sx. cement., 2 sx. cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION

SEP 5 1963

9-5-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Messman-Rinehart Oil Company
Address 1432 Wichita Plaza Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) ~~or power of attorney~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland
1432 Wichita Plaza Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of September 1963

Barbara J. Scott
Barbara J. Scott, Notary Public.

My commission expires December 1, 1964



NO. 1 REDETZKE "D"Well Record:

Location: App. NE/4 NW/4 H/4
Section 12-23S-10W
Reno County, Kansas

Commenced: August 7, 1963

Completed: August 17, 1963

Operator: Hossman-Rinehart Oil Company
1432 Wichita Plaza Bldg.
Wichita 2, Kansas

Elevation: 1880' K/B

Production: D & A

Contractor: Hossman-Rinehart Oil Company
1432 Wichita Plaza Bldg.
Wichita 2, Kansas

Casing Record: 8-5/8" @ 296' w/160 sx. cement

*** LOG ***

Clay and Post Rock, Shale	70	
Sand	85	
Shale & Shells	296	
Shale & Red Bed	720	
Anhydrite	755	
Shale & Shells	965	
Shale & Lime Shells	1405	
Shale & Lime	1750	
Lime	1975	
Lime & Shale	2615	
Lime	2715	
Lime & Shale	2805	
Lime	2895	
Shale & Sand	3005	
Brown Lime	3021	
Lime (Lansing)	3055	
Lime	3250	
Lime & Conglomerate	3315	
Conglomerate and Sand	3320	
Conglomerate	3345	
Lime	3354	R.T.D.

Sample Tops:
Chase Group 1484' (-436)
Tarkio 2348' (-468)
Howard Lime 2583' (-703)
Topeka 2597' (-717)
Hessner Shale 2914' (-1034)
Toronto 2933' (-1053)
Douglas 2946' (-1066)
Brown Lime 3005' (-1125)
Lansing 3029' (-1143)
Conglomerate Shale 3308' (-1428)
Conglomerate Sand 3323' (-1443)
Arbuckle 3342' (-1462)

The undersigned, HESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

HESSMAN-RINEHART OIL COMPANY

By: J. A. Gilliland

J. A. Gilliland

Subscribed and sworn to before me
this 29th day of August, 1963

Barbara J. Scott
Barbara J. Scott, Notary Public

My Commission Expires: December 1, 1964

RECEIVED
STATE CORPORATION COMMISSION

SEP 5 1963

CONSERVATION DIVISION
Wichita, Kansas