

15-009-07184-0500

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Barton County, Sec. 6 Twp. 16 Rge. 11 ~~25~~ W (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW SW

Lease Owner Globe Oil & Refining Co.

Lease Name Woydziak Well No. 1

Office Address 301 So. Market, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed November 19, 1954

Application for plugging filed February 9, 1954

Application for plugging approved February 10, 1954


Plugging commenced February 25, 1954

Plugging completed March 5, 1954

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production October 31, 1952

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Warren H. Horner

Producing formation Arbuckle Depth to top 3316 Bottom Total Depth of Well 3331 Feet

Show depth and thickness of all water, oil and gas formations. P.B. 3067

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	oil	3316	3331	8 5/8	522	None
				5 1/2	3331	2627'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sand bridged hole from 3067-3030. Cement bottom of hole with 5 sacks cement from 3030-3000. Mudded hole to 275', set rock bridge from 275 to 260 and run 20 sacks cement from 260 to 205'. Mudded hole to 30' and ran 10 sacks cement to cellar.

3-11-54

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Globe Oil & Refining Co.  
Address 301 South Market  
Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Leo Ross (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Leo Ross*

301 South Market, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 21st day of July, 1954

My commission expires July 21, 1954 *Francis Leslie* Notary Public

PLUGGING  
PAGE 6 OF 11  
BOOK PAGE 12 LINE 43

15-009-07184-0000

WELL LOG

Company: Globe-Wm. Graham  
Lease: #1 Woydziak  
SW SW SW Sec. 6-16-11W  
Barton County, Kansas  
Contractor: The Phil-Han Oil Company

Commenced: 11-2-45  
Completed: 11-19-45

<u>Formation</u>	<u>Depth</u>
Surface soil & shells	278
Shale	420
Sand	450
Shale & shells	522
Red rock	745
Anhydrite lime	765
Red rock & shale	1190
Salt	1440
Shale & lime streaks	1540
Shale & lime	1775
Lime	2060
Lime & shale	2210
Sandy lime streaks & shale	2310
Lime & shale	2620
Lime	2675
Lime & shale	2729
Lime	2808
Lime & shale	2854
Lime	2937
Lime & shale streaks	3009
Lime	3085
Lime & shale	3102
Lime, shale & red bed	3111
Lime	3239
Lime & shale streaks	3269
Lime	3308
Shale	3310
Lime Arb. erosion	3315
Shale & lime	3330
Lime	3331 T.D.

CASING RECORD:

8 5/8" 522 Cem. 180 sacks  
5 1/2" 3331' Cem. 75 sacks

**PLUGGING**  
 FILE SEC 6 T 16 R 11W  
 ROCK PAGE 12 LINE 43

2-10-54