

15-009-21944-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Barton SEC. 6 TWP. 16S RGE. 11W E/W  
Location as in quarters or footage from lines:

SE NE NW


Lease Owner Energy Three, Inc.

Lease Name Esfeld Well No. #2

Office Address P.O. Box 1505 Great Bend, Kansas 67530

Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_

Date Well Completed \_\_\_\_\_

Application for plugging filed \_\_\_\_\_

Plugging commenced 10-1-81

Plugging completed 10-7-81

Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3390'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	320'	none
				4-1/2"	3389'	2491'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Moved in on location, plugged off bottom with sand to 2875' and set 4 sacks cement.  
Got 21" stretch, shot casing @2843', 2719', 2595' and 2510'. Pulled 59 joints  
of casing. Plugged well with 5 sacks hulls, 25 sacks gel, 8-5/8" plug, and  
140 sacks 50/50 pos, 2% gel, 3% cc. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso

R. Darrell Kelso Chase, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of October, 19 81

My Commission expires



Irene Hoover RECEIVED  
STATE CORPORATION COMMISSION  
Notary Public.

10-15-81  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLER'S WELL LOG

15-009-21944-0000

DATE COMMENCED: 5-31-80  
DATE COMPLETED: 6-6-80

Energy Three Inc.  
Esfeld #2  
SE NE NW Sec. 6-16-11  
Barton County, KS

ELEVATION: K.B.

FORMATION DATA

746' Anhydrite

2902-2907'	Shale
2907-2920'	Lime
2920-2936'	Lime
2936-2994'	Shale
2994-3008'	Lime & Shale
3008-3270'	Lime
3270-3295'	Lime & Shale
3295-3326'	Shale, Lime, Chert & Sand
3326-3390'	Dolomite
3390'	RTD

Anhydrite 746'

Heebner	2902'
Toronto	2920'
Douglas	2936'
Brown Lime	2994'
Kansas City	3008'
Base Kansas City	3270'
Conglomerate	3295'
Arbuckle	3326'
RTD	3390'

SURFACE PIPE:

Set @ 320' 8 5/8" 28#  
used casing w/175 sks  
common 2% Gel 3% c.c.

PRODUCTION PIPE:

Ran 82 jts. 4 1/2" 9 1/2#  
casing. Set @ 3389'  
w/100 sks common by Howco  
P.D. 6:15 p.m.  
6-6-80

A F F I D A V I T

STATE OF KANSAS )  
COUNTY OF BARTON ) ss.


Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 9 1981

CONSERVATION DIVISION  
Wildlife Kansas

*Larry Curtis*

Subscribed and sworn to before me this 11th day of June 1980.



*Sandra Nichols*  
Notary Public

My commission Expires: 12-10-83