

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-093-21128-0000

LEASE NAME Bentrup Gas Unit /C/

WELL NUMBER 2HI

3880 Ft. from S Section Line

1360 Ft. from E Section Line

SEC. 9 TWP. 24S RGE. 35 (E) or (W)

COUNTY Kearny

Date Well Completed 3/21/91

Plugging Commenced 11/24/97

Plugging Completed 11/24/97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Amoco Production Company

ADDRESS PO Box 800 Room 924 Denver, CO 80201

PHONE# (303) 830-5323 OPERATORS LICENSE NO. 5952

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/24/97 (date)

by M. Mier (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Chase Depth to Top 2428' Bottom 2690' T.D. 2690'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface			8 5/8"	824'	0
	Production			5 1/2"	2690'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped 292 sx 65/35 Class C/POZ cement from 2690' to 4' down 5.5" casing. Place 1000 lbs hulls in lead slurry to block off slots. Pumped 8 sx cement down casing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. RECEIVED

Address _____ KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Amoco Production Company DEC 03 1997

STATE OF Colorado COUNTY OF Denver, ss. 12-3-97

Susan R. Potts (Employee of Operator) on (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Susan R. Potts

(Address) PO Box 800 Room 924 Denver, CO 80201

SUBSCRIBED AND SWORN TO before me this 2nd day of December, 19 97

My Commission Expires: January 4, 2001 Notary Public 110 BROADWAY
DENVER, CO 80201

9 24 35 W

15-093-21128-0060

DRILLERS LOG

AMOCO PRODUCTION COMPANY
BENTRUP GU "C" NO. 2 HI
SECTION 9-T24S-R35W
KEARNY COUNTY, KANSAS

COMMENCED: 01-10-91
COMPLETED: 01-13-91

SURFACE CASING: 816' OF 8 5/8"
CMTD W/300 SX 35/65, POZ/C, 6% D-20,
3% SI, 1/4#/SX D-29; TAILED IN W/
150 SX "C", 3% SI, 1/4#/SX D-29

FORMATION	DEPTH
SURFACE HOLE	0- 824
SAND & RED BED	824-885
RED BED	885-1135
GLORIETTA SAND	1135-1310
SHALE & LIME	1310-2690 RTD

1-16-1991

I DO HEREBY CERTIFY THAT THE FOREGOING STATEMENTS ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

CHEYENNE DRILLING, INC.
A.J. Jacques
A.J. JACQUES

STATE OF KANSAS :ss:

SUBSCRIBED AND SWORN TO BEFORE ME THIS 14TH DAY OF JANUARY, 1991.

BECKY J. WHETSTONE
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 4/29/91

Becky J. Whetstone
BECKY J. WHETSTONE, NOTARY PUBLIC

KCC

JAN 17 1991