

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-093-20,961-0000

LEASE NAME Singleton

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-I

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR Plains Petroleum Operating Co.

SEC. 30 TWP. 24S RGE. 35 ~~W~~ or (W)

ADDRESS P.O. Box 15278 Lakewood, CO 80215

COUNTY Kearny

PHONE# (303) 969-9325 OPERATORS LICENSE NO. 4253

Date Well Completed 1-26-89

Character of Well D&A

Plugging Commenced 1-26-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-26-89

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City - Richard Lacy on loc. during plugging

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Chase Depth to Top 2373' est Bottom 2650' T.D. 2650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Fresh wtr sands	Water	Surface	371'	8 5/8"	371'	-

2-17-89
RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1989
COMMISSION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the cement or other plugs were placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Drill pipe stuck @ 1500', lost circ w/ bit @ 2650'. Pump 50 sacks Class "C" cmt down drillpipe. Displace wiper plug w/ 29 1/2 bbls drlg mud to top of drill collars @ 2180'. Pressure to 1000 psi. Backoff drillpipe @ 1005'. Spot 50 sks Class "C" cmt from 835-935'. Spot 50 sks Class "C" cmt 312-412'. Spot 10 sks Class "C" cmt from 0-30'. Pump 10 sks Class "C" cmt in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Cheyenne Drilling, Inc. License No. 5382

Address P.O. Box 916, Garden City, KS 67846

STATE OF Colorado COUNTY OF Jefferson, ss.

Jeffrey E. Carlson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jeffrey E. Carlson

(Address) P.O. Box 15278, Lakewood, CO 80215

SUBSCRIBED AND SWORN TO before me this 14th day of February, 19 89

Nancy Buckingham
Notary Public

My Commission Expires: 4 October 1990

DRILLERS LOG

PLAINS PETROLEUM OPERATING CO.
 SINGLETON #1-1
 SECTION 30-T24S-R35W
 KEARNY COUNTY, KANSAS

COMMENCED: 01-23-89
 COMPLETED: 01-26-89

SURFACE CASING: 371' OF 8 5/8"
 CMTD W/100 SX LITE "C", 2% C.C.
 1/4# FLOCEL, TAILED IN W/200 SX
 PREM PLUS, 2% C.C., 1/4#/SX
 FLO-CEL

FORMATION	DEPTH
SURFACE HOLE	0- 371
SAND & CLAY	371-1390
GLORIETTA SAND	1390-1520
SAND & RED BED	1520-1595
SHALE	1595-1848
ANHYDRITE	1848-1858
SHALE	1858-2226
LIME & SHALE	2226-2455
SHALE	2455-2650 RTD

I DO HEREBY CERTIFY THAT THE FOREGOING STATEMENTS ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

CHEYENNE DRILLING, INC.

A. J. Jacques

A. J. JACQUES

STATE OF KANSAS :ss:

SUBSCRIBED AND SWORN TO BEFORE ME THIS 26TH DAY OF JANUARY, 1989.

PAM KAISER
 NOTARY PUBLIC
 STATE OF KANSAS
 MY APPT. EXPIRES 3-5-91

Pam Kaiser
 PAM KAISER, NOTARY PUBLIC

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 1 1989
 2-1-1989
 PERMITS DIVISION
 Wichita, Kansas

A