

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-093 20,855-0000

LEASE NAME White GU

WELL NUMBER E #1

SPOT LOCATION C N/2 of SW/4

SEC. 12 TWP 24 RGE. 36 or (W)

COUNTY Kearny

Date Well Completed 2-26-86

Plugging Commenced 1-31-89

Plugging Completed 2-1-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Amoco Production Co.

ADDRESS Box 800, Denver, CO 80201

PHONE # (316) 356-1237 OPERATORS LICENSE NO. 5952

Character of Well gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks.

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Council Grove Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	830'	0'
Production				5 1/2"	2904'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Set CYBP @ 2604' and capped w/2 Skts.

Cement Pump 2 sks. Gel and 20 Skts. cement 1600' to 1400'
Displace w/gel to 860' pumped 20 Skts. cement 860' to 660'
Displaced w/gel to 40' - put bridge and 5 Skts. cement 40' to 5'
Fill 8 5/8" from 114' to 5' w/15 Skts. cement
Cut off 8 5/8" and 5 1/2", 5' below ground level and cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497

Address Box F, Sublette, Ks. 67877

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877

FEB 6 1989
2-6-89
CONSERVATION DIVISION
Wichita, Kansas



SUBSCRIBED AND SWORN TO before me this 2nd day of Feb., 19 89

Sondra L. Eves
Notary Public

My Commission expires: 12-6-92