

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Finney SEC. 7 TWP. 24S RGE. 34 ☒ W
Location as in quarters or footage from lines:
1260' FWL & 1280' FNL

X			

Locate Well
correctly on above
Section Platt.

Lease Owner Amoco Production Company
Lease Name Crawford Gas Unit Well No. 3
Office Address P. O. Box 432 Liberal, KS 67901
Character of Well (Completed as Oil, Gas or Dry Hole): Gas
Date Well Completed 6-18-80
Application for plugging filed 12-14-82
Plugging commenced 1-28-83
Plugging completed 2-4-83
Reason for abandonment of well or producing formation Formation no longer productive
Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well KCC-KDHE Dist. Office
Producing formation Council Grove Depth to top 2708 bottom 3050 T.D. 3050
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Council Grove</u>	<u>Gas</u>	<u>2708</u>	<u>3050</u>	<u>8-5/8</u>	<u>616</u>	<u>0</u>
				<u>5-1/2</u>	<u>3050</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set. Set cast iron bridge plug at 2700', cap with 2 sacks cement. Pump 70 sacks cement 600' to 0'. Cut 8-5/8" and 5-1/2" casing 6' below surface, fill top of 8-5/8" casing with four sacks cement. Weld plate on 8-5/8" casing. Restore surface to natural state.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwest Casing Pullers

STATE OF Kansas COUNTY OF Seward, ss.

R. C. Carlson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. C. Carlson
P. O. Box 432 Liberal, KS 67901
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of April, 19 83

V. K. Bruce
Notary Public.

My Appointment expires: 4-28-85

RECEIVED
STATE CORPORATION COMMISSION

APR 15 1983

CONSERVATION DIVISION
Wichita, Kansas