

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Finney

County, Sec. 22 Twp. 24S Rge. (EX) 34(W)

Location as "NE/CNW/SW" or footage from lines. C NE SW

Lease Owner Shell Oil Company

Lease Name P. A. Brown "A" Well No. 1-22

Office Address Post Office Box 744 - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 18 19 59

Application for plugging filed July 21 19 59

Application for plugging approved (Verbal) June 19 19 59


Plugging commenced June 19 19 59

Plugging completed June 20 19 59

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation Mississippian Depth to top 4838 Bottom - Total Depth of Well 5101 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	852'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full of heavy rotary mud; ran drill pipe in hole & set cement plugs with total 175 sax Pozmix as follows: 4565-4340, 2305-2075, 870-800 & 25-0.

- 5101-4565 Mud
- 4565-4340 Cement
- 4340-2305 Mud
- 2305-2075 Cement
- 2075-870 Mud
- 870-800 Cement
- 800-25 Mud
- 25-0 Cement

STATE CORPORATION COMMISSION
JUL 23 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Helmerich & Payne, Inc.

Address First National Building - Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.

A. W. Weber (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. W. Weber

Post Office Box 744 - Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of July, 1959

My commission expires January 28, 1961

Notary Public.

24-7366-5 3-53-20M

PLUGGING
FILE SEC 22 T 24 R 34W
BOOK PAGE 53 LINE 1

SHELL-P. A. BROWN "A" NO. 1-22
C NE SW Section 22-24S-34W
WILDCAT, HUGOTON FIELD (AREA 1)
FINNEY COUNTY, KANSAS

Casing Record

8 5/8" cem 852 with 750 sax; cem. circ.

- 0 - 637 sand & shale
- 1167 red beds
- 1810 sand & shale
- 2139 shale & sand
- 2458 shale & lime
- 2545 shale & sandy lime
- 2706 red bed & shale
- 2795 lime & sand
- 2918 shale & lime
- 2986 red bed & lime streaks
- 3078 lime
- 3122 shale & lime
- 3238 shale
- 3305 lime
- 3410 shale, limey
- 3525 shale
- 3744 chalk & shale
- 3860 shale, chalk & lime
- 3943 shale & lime
- 4062 lime & chalk
- 4128 lime
- 4184 lime, shale & chalk streaks
- 4264 lime
- 4310 lime & shale
- 4395 shale & lime
- 4440 lime
- 4523 lime & shale
- 4592 shale
- 4631 lime
- 4690 lime & shale
- 4739 shale
- 4785 lime & shale
- 4812 sand w/ streaks of lime, good oil stain.
- 4919 lime & shale
- 5085 lime
- 5100 lime & shale
- 5100=5101 SLC T.D.

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

RECORDED
STATE COMMISSION
JUL 23 1959
CONSERVATION DIVISION
Wichita, Kansas

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Shell-P. A. Brown "A" Area 1 No. 1-22 well, located in Section 22-24S-34W, Finney County, Kansas.

PLUGGING
FILE SEC 22 T. 24 R. 34W
BOOK PAGE 53 LINE 1

SHELL OIL COMPANY

by A. W. Weber
District Superintendent

Subscribed and sworn to before me a Notary Public this 21st day of July, 1959.

My commission expires January 28, 1961

L. Mont Biers