

STATE OF KANSAS
STATE CORPORATION COMMISSION
200, Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-055-20,613-0000

LEASE NAME Orange Brown

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2975' Ft. from S Section Line

2975' Ft. from E Section Line

SEC. 21 TWP. 24 RGE. 34 or (W)

COUNTY Finney

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500, Wichita, Kansas 67202

PHONE# (316) 265-9697 OPERATORS LICENSE NO. 5003

Date Well Completed 2-10-86

Character of Well D&A

Plugging Commenced 10-12-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-14-88

The plugging proposal was approved on October 11, 1988 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 4730 Bottom 4868

Show depth and thickness of all water, oil and gas formations.

RECEIVED 102
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

OCT 24 1988

Formation	Content	From	To	Size	Put In	Pulled out
		0	1999	8-5/8"	1999'	
		0	5102	5-1/2"	5102	

CONSERVATION DIVISION
Wichita, Kansas
2014

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Rig up Welex to set plug and shoot off casing. Set CIBP @ 4760' in 5-1/2" casing. Place 3 sacks of cement on top of CIBP with dump bailer. Welex made cut in 5-1/2" casing @ 2900', casing did not pull free. Made cut @ 2014'. Casing pulled free. Pull and lay down 47 joints of 5-1/2" OD casing. Go in hole with 65 joints of 2-7/8" tubing. Mix gel and
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hayes Well Service License No. 5429

Address Attica, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

John Roger McCoy (Employee of Operator) or Operator of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) John Roger McCoy

(Address) 110 S. Main, Suite 500
Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 21st day of October, 19 88

Deborah Ann Paulus
Notary Public

My Commission Expires: 1-8-92



circulate hole as per KCC order.

Rig up Halliburton. Set plugs as follows: Using 60-40 Pozmix, 6% gel, place the bottom of a 50 sack plug @ 2000', the bottom of a 30 sack plug @ 850' and a 10 sack plug from 40' to 3' below ground level.