

RECEIVED

RECEIVED

SEP-20-2002

SEP 16 2002  
9-16-02  
KCC WICHITA

KCC WICHITA

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-093-20012-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Geo. R. Shaw KCC LICENSE # 5062 4/03

ADDRESS 150 N. Main, Suite 1007 (owner/company name) CITY Wichita (operator's)

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (620) 275-7888

LEASE Smalley WELL# 1-34 SEC. 34 T. 24S R. 38 (East/West)

app- SE - SPOT LOCATION/QQQQ COUNTY Kearny

1320 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1420 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 10.750" SET AT 217' CEMENTED WITH 225 SACKS

PRODUCTION CASING SIZE 7" SET AT 2380' CEMENTED WITH 200 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 5.5" slotted liner from 2367'-2471'

ELEVATION 3157' T.D. 2465' PSTD 2465' ANHYDRITE DEPTH 1880' - est.  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set a CIBP @ 2300' w/2sx cement on top, load casing w/water and pressure test, perforate 7" casing at 660', cement backside of 7" with cement and leave cement to surface inside 7". cement to be 60/40 Pozmix w/6% gel.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? N.A.

If not explain why? none available

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ron Osterbuhr PHONE# ( ) 620-275-7888

ADDRESS P.O. Box 1152 City/State Garden City, KS 67846

PLUGGING CONTRACTOR Will advise Border-Line Well Service KCC LICENSE # 7840 4/03

ADDRESS 2260 N Road I Ulysses, KS 67880 (company name) PHONE # ( ) 620-356-8381 (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Will advise

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 09/13/2002 AUTHORIZED OPERATOR/AGENT: Ronald Osterbuhr  
(signature)



## *Kansas Corporation Commission*

*Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner*

### **NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Shaw, George R.  
1001 Commerce Bank Center  
150 N. Main  
Wichita, KS 67202

September 20, 2002

Re: SMALLEY #1-34  
API 15-093-20012-00-00  
E2W2SE 34-24S-38W, 1320 FSL 1420 FEL  
KEARNY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(316) 225-8888

Sincerely  
A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams  
Production Supervisor