

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22145-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 9-24S-5E
2270 feet from S Section Line, 2310 feet from E Section Line
Lease Name: RAMSEY Well #: 6
County: BUTLER Total Vertical Depth: 2620 feet

Operator License No.: 5120 String Size Depth (ft) Pulled (ft) Comments
Op Name: RANGE OIL COMPANY, INC. PROD 4.5 2615 100 SX
Address: 9412 E. CENTRAL PO BOX 781775 SURF 8.675 207 210 SX
WICHITA, KS 67278

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/13/2016 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: ALAN NATION Company: RANGE OIL COMPANY Phone: (620) 222-4304

Proposed Plugging Method: As per KCC instructions

Plugging Proposal Received By: JONATHAN HILL Witness Type: NONE
Date/Time Plugging Completed: 07/14/2016 12:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

***Per operator's CP-4:
Ran tubing to 2470' and pumped 25 sacks of cement with 150 pounds of hulls and 3% CaCl.
Pulled tubing and perforated casing at 257'. Ran tubing downhole and tagged bottom plug at 2450'. Pulled tubing back to 257' and pumped 80 sacks of cement which circulated out 4.5" casing. Pulled tubing out and pumped 80 sacks of cement down 4.5" casing and filled to surface.

Perfs:

Top	Bot	Thru	Comments
2524	2530		

Remarks: KCC PERSONAL DID NOT WITNESS PLUGGING OPERATIONS. CEMENTING COMPLETED BY QUALITY WELL SERVICE, ELLINWOOD, KS. TICKET #: 6538

Plugged through: TBG

District: 02

Signed *Jonathan Hill*
(TECHNICIAN)

Form CP-2/3
AUG 18 2016
no