

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-20780-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 20-29S-7W  
4950 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: WALTERS Well #: 1  
County: KINGMAN Total Vertical Depth: 4143 feet

Operator License No.: 6236  
Op Name: MTM PETROLEUM, INC.  
Address: 2370 SOUTH STATE ROAD 14 PO BOX  
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4127		150 SX
SURF	8.625	259		200 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/12/2016 12:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: \_\_\_\_\_

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/18/2016 2:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

BACKSIDE OF CASING SQUEEZED FROM 690'-0'. PUMPED 25 SK PLUG TO BOTTOM SI 600#. PERF'D CASING AT 1100'. RAN TUBING TO 1100' & FILLED INSIDE OF 4 1/2" TO SURFACE. LAYED DOWN TUBING & TIED ONTO 4 1/2" CASING TO PUMP ADDITIONAL 25 SX CEMENT. SI 200#. CEMENT FILL INSIDE 8 5/8" CASING, PUMPED 10 SXS CEMENT LET SET OVERNITE, PUMP ANOTHER 30 SX CEMENT. CASINGS FULL.

Perfs:


Top	Bot	Thru	Comments
4127	4128		

Remarks: COMMON CEMENT

Plugged through: TBG


District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

Form CP-2/3

AUG 18 2016  


1/2K