

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-19301-00-00
Spot: NWNESW Sec/Twnshp/Rge: 11-24S-18E
2528 feet from S Section Line, 3464 feet from E Section Line
Lease Name: HOWLAND Well #: 2
County: ALLEN Total Vertical Depth: 900 feet

Operator License No.: 33783
Op Name: MICHAEL DRILLING LLC
Address: 1304 E ST PO BOX 402
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	900		20 SX
SURF	7	20		5 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/31/2016 12:00 AM
Plug Co. License No.: 33783 Plug Co. Name: MICHAEL DRILLING LLC
Proposal Rcvd. from: RCK MICHAEL Company: _____ Phone: (620) 496-7795

Proposed Plugging Method: RUN 1" TO T.D. PUMP 10 SX, PULL TO 500 PUMP 10 SX, PULL TO 250 FILL TO SURFACE
BACK SIDE TO 250 FILL TO SURFACE
RUN DOWN

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/31/2016 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2" casing from TD to surface. Pulled 1" pipe. Ran 1" pipe down the backside of the 2" casing inside the 7" casing. Pumped and circulated cement through the 1" pipe from TD to surface. Pulled 1" pipe and topped well off with cement. A total of 75 sacks of cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
850	860		
RECEIVED KCC DIST # 3 AUG 09 2016 CHANUTE, KS RD			

Remarks:

Plugged through: TBG

District: 03

Signed: [Signature] E.C.R.S.
(TECHNICIAN)

KCC WICHITA
AUG 11 2016
RECEIVED

Form CP-2/3

AUG 18 2016
[Signature]