

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-001-19280-00-00  
Spot: SWNWSW Sec/Twnshp/Rge: 11-24S-18E  
1618 feet from S Section Line, 4933 feet from E Section Line  
Lease Name: HOWLAND Well #: 13  
County: ALLEN Total Vertical Depth: 900 feet

Operator License No.: 33783  
Op Name: MICHAEL DRILLING LLC  
Address: 1304 E ST PO BOX 402  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	900		20 SX
SURF	7	20		5 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/31/2016 12:00 AM  
Plug Co. License No.: 33783 Plug Co. Name: MICHAEL DRILLING LLC  
Proposal Rcvd. from: RICK MICHAEL Company: \_\_\_\_\_ Phone: (620) 496-7795

Proposed Plugging Method: RUN 1" TUBING TO T.D. PUMP 10 SX , PULL TO 500' PUMP 10 SX , PULL TO 250 FILL TO SURFACE . RUN 1" TUBING DOWN BACK SIDE OF 2TO 300 FT FILL TO SURFACE .

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/31/2016 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2" casing from TD to surface. Pulled 1" pipe. Ran 1" pipe down the backside of the 2" casing inside the 7" casing to 350'. Pumped and circulated cement through the 1" pipe from 350' to surface. Pulled 1" pipe and topped well off with cement. A total of 90 sacks of cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
860	870		
RECEIVED KCC DIST # 3 AUG 09 2016 CHANUTE, KS RD			

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]  
(TECHNICIAN)

KCC WICHITA  
AUG 11 2016  
RECEIVED

Form CP-2/3  
AUG 18 2016  
[Signature]