

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-19281-00-00
Spot: SENWSW Sec/Twnshp/Rge: 11-24S-18E
1615 feet from S Section Line, 4666 feet from E Section Line
Lease Name: HOWLAND Well #: 14
County: ALLEN Total Vertical Depth: 900 feet

Operator License No.: 33783
Op Name: MICHAEL DRILLING LLC
Address: 1304 E ST PO BOX 402
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	900		20 SX
SURF	7	20		5 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/31/2016 12:00 AM
Plug Co. License No.: 33783 Plug Co. Name: MICHAEL DRILLING LLC
Proposal Rcvd. from: RICK MICHAEL Company: _____ Phone: (620) 496-6257

Proposed Plugging Method: RUNN 1" TUBING TO T.D. PUMP 10 SX , PULL 500' PUMP 10 SX PULL TO 250' PUMP TO SURF . RUN 1" DOWN BACK SIDE OF 2" TO 250 FT FILL TO SURFACE

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/31/2016 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2" casing from TD to surface. Pulled 1" pipe. Ran 1" pipe down the backside of the 2" casing inside the 7" casing to 500'. Pumped and circulated cement through the 1" pipe from 500' to surface. Pulled 1" pipe and topped well off with cement. A total of 75 sacks of cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
860	870		

RECEIVED
KCC DIST # 3
AUG 09 2016
CHANUTE, KS
RD

Remarks:

Plugged through: TBG

District: 03

KCC WICHITA

AUG 11 2016

RECEIVED

Signed [Signature] E.L.A.S.
(TECHNICIAN)

Form CP-2/3

AUG 18 2016
[Signature]