

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-01601-00-00
Spot: SENWSESE Sec/Twnshp/Rge: 11-24S-9E
750 feet from S Section Line, 750 feet from E Section Line
Lease Name: OLSON-ANDERSON Well #: 14
County: GREENWOOD Total Vertical Depth: 2190 feet

Operator License No.: 3599
Op Name: JB NORDMEYER, LLC DBA OLSON-AN
Address: 2253 P RD
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.625	2163		200 SX
SURF	8.25	1613		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/08/2016 9:00 AM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Rcvd. from: BARNEY NORDMEYER Company: _____ Phone: (620) 583-7548

Proposed Plugging Method: SET 50 FOOT PLUG ABOVE BARTLESVILLE FORMATION, GEL SPACING, 50 FOOT PLUG ABOVE DOUGLAS FORMATION, GEL SPACING, 200 FEET TO SURFACE WITH PERFORATIONS IN PLUG AT DOUGLAS AND AT 200 FEET.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 08/05/2016 1:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1875' pumped 25 sxs cement, pulled tubing to 935' pumped 25 sxs cement, pulled tubing to 216' pumed 55 sxs cement to surface, casing shot @ 935' & 200', gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
2155	2190		

RECEIVED
KCC DIST # 3
AUG 08 2016
CHANUTE, KS
MHT

Remarks:

Plugged through: TBG

District: 03

KCC WICHITA

Signed

Michael Heffern
(TECHNICIAN)

AUG 11 2016

RECEIVED

Form CP-2/3

AUG 18 2016

MHT