

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-22369-00-00
Spot: NWSWNWSE Sec/Twnshp/Rge: 25-17S-29W
1821 feet from S Section Line, 2345 feet from E Section Line
Lease Name: SCHULTZ 25 Well #: 1
County: LANE Total Vertical Depth: 4660 feet

Operator License No.: 34158
Op Name: O'BRIEN RESOURCES, LLC
Address: PO BOX 6149
SHREVEPORT, LA 71136

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4115		WITH 2 SX CMT
DVT		2180		WITH 575 SX CMT
PROD	4.5	4660	0	WITH 625 SX CMT
SURF	8.625	271		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/19/2016 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RANDY Company: O'BRIEN RESOURCES Phone: (785) 639-2099

Proposed Plugging Method: CIBP @ 4250' WITH 2 SX CMT. FILL UP CMT TO SURFACE. CIRCULATE CMT TO SURFACE. TIE ON BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/19/2016 10:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4115' WITH 2 SX CMT. (TAGGED FL AT 2750') 6 BBL FLUID DOWN 4 1/2" FROM 2750' TO 2300'. FILL 4 1/2" CASING WITH CMT FROM 2300' TO SURFACE USING 150 SX CMT. (BLEED AIR OFF TWICE WHILE FILLING THE CASING). PRESSURE TO 500#. HOLDING. PUMP 10 SX CMT DOWN THE ANNULUS TO 300#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
4348	4351		
4332	4338		
4319	4322		
4300	4311		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
JA

(TECHNICIAN)

RECEIVED
JUL 21 2016
KCC DODGE CITY

Form CP-2/3
AUG 18 2016

MA