

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-21713-00-00
Spot: E2W2SESE Sec/Twnshp/Rge: 3-31S-12W
660 feet from S Section Line, 750 feet from E Section Line
Lease Name: HAAS Well #: 2
County: BARBER Total Vertical Depth: 4656 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4520 | | |
| PROD | 4.5 | 4597 | 2150 | WITH 100 SX CMT |
| SURF | 8.625 | 347 | | WITH 300 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/15/2016 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (620) 886-2419

Proposed Plugging Method: SAND ABCK TO 4420' & 4 SX CMT. PLUG AT 690' WITH 10 SX GEL & 50 SX CMT. PLUG AT 390' WITH 100 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: PARTIAL
Date/Time Plugging Completed: 07/15/2016 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4372' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 690' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4546 | 4551 | | |
| 4468 | 4478 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)
SR

RECEIVED
JUL 25 2016
KCC DODGE CITY

Form CP-2/3
AUG 18 2016
no