

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-23275-00-02
Spot: SWNENW Sec/Twnshp/Rge: 22-33S-6E
4181 feet from S Section Line, 3440 feet from E Section Line
Lease Name: DRAKE A Well #: 4
County: COWLEY Total Vertical Depth: 3120 feet

Operator License No.: 30169
Op Name: DOUBLE "D" OIL COMPANY, INC.
Address: 2009 JEAN CT
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3119		200 SX
PROD	4.5	3120		
SURF	8.625	300		80 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/16/2016 8:00 AM
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL AND/OR PENNY M. DBA MCPHERSON DRILLING
Proposal Rcvd. from: DONALD BUTLER Company: DOUBLE D OIL CO Phone: (620) 221-3570

Proposed Plugging Method: AS PER KCC RULES & REGS/ CMT 50' ABOVE TOP PERF, CIRC 350'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/16/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG, CIRCULATED HOLE CLEAN TO 3110'. WITH TUBING @ 3110', MCPHERSON DRILLING MIXED & PUMPED 25 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 2900'. RIH ON WIRELINE @ 350', PERFORATED 350-351 (2 HOLES) RIH W/TBG @ 360', MCPHERSON DRILLING ESTABLISHED CIRCULATION, MIXED & PUMPED 110 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #34352, & 34368.

Perfs:

Top	Bot	Thru	Comments
2964	2968	CSG	

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

Form CP-2/3

AUG 18 2016

JK
JK