

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-02151-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 14-34S-4E
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: CRAIN Well #: 1
County: COWLEY Total Vertical Depth: 3229 feet

Operator License No.: 3661
Op Name: GROVES, PHIL DBA PHIL GROVES OIL
Address: 811 E MADISON AVE PO BOX 571
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3209		
PROD	4.5	3229		0 SX
SURF	8.63	0		220 SX
SURF	8.625	258		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/10/2016 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: PHIL GROVES Company: PHIL GROVES OIL Phone: (620) 442-0480

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 06/13/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

PACKER & TUBING HUNG UP IN HOLE. RIH ON WIRELINE @ 1010', CUT TUBING. LAYED DOWN TUBING. RIH W/TBG @ 1010', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. LAYED DOWN TUBING. TAGGED CEMENT PLUG @ 827'. 6-14-2016, RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 310'. RIH W/TBG @ 310', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 150 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TUBING, TOPPED WELL BACK TO SURFACE W/20 SXS.

Perfs:

Top	Bot	Thru	Comments
3028	3034	CSG	
2892	2898	CSG	
2854	2862	CSG	

Remarks: TA LETTERS/ COMPLIANCE/ 10 YR RULE/ APPROX. 1800' TUBING & PACKER LEFT IN HOLE

Plugged through: TBG

District: 02

KCC WICHITA
AUG 03 2016
RECEIVED

DUANE KRUEGER
(TECHNICIAN)

✓ SK

AUG 18 2016
Form CP-2/3
AUG 18 2016