

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-23103-00-00  
Spot: NESESENW Sec/Twnshp/Rge: 14-34S-4E  
3210 feet from S Section Line, 2840 feet from E Section Line  
Lease Name: VITA CRAIN Well #: 10  
County: COWLEY Total Vertical Depth: 3260 feet

Operator License No.: 3661  
Op Name: GROVES, PHIL DBA PHIL GROVES OIL  
Address: 811 E MADISON AVE PO BOX 571  
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3230		150 SXS CMT
SURF	8.63	202		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/15/2016 8:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: PHIL GROVES Company: PHIL GROVES OIL Phone: (620) 442-0480

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/17/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 3023', 6-16-2016, CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 30 SXS 60/40 POZMIX 4% GEL 3% CC & DISPLACED IN CASING . LAYED DOWN TUBING. TAGGED CEMENT PLUG @ 2975'. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES @ 250'. WELL WOULD NOT CIRCULATE. RIH W/TBG @ 270', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 40 SXS 60/40 POZMIX 4% GEL 3% CC 1/2 # POLY FLAKES W/HULLS. CEMENT CIRCULATED. LAYED DOWN TUBING, SWEDGED INTO 4.5" & PUMPED 12 SXS 60/40 POZMIX 4% GEL 3% CC, SIP 500#. 6-17-2016, RIH ON BACKSIDE W/1" TBG @ 250', CONSOLIDATED OILWELL ESTABLISHED CIRCULATION, MIXED & PUMPED 95 SXS 60/44 POZMIX 2% CC TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #5170, 51301.

Perfs:

Top	Bot	Thru	Comments
3178	3220		CSG
3003	3020		

Remarks: TA LETTERS/ COMPLIANCE/10 YR RULE

Plugged through: TBG

District: 02

Signed

Duane Krueger  
(TECHNICIAN)

KCC WICHITA  
AUG 03 2016  
RECEIVED

Form CP-2/3  
AUG 18 2016  
no

✓