

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-071-20727-00-00
Spot: NW Sec/Twship/Rge: 15-20S-40W
4055 feet from S Section Line, 3911 feet from E Section Line
Lease Name: HARRIS A Well #: 2
County: GREELEY Total Vertical Depth: 2860 feet

Operator License No.: 4894
Op Name: HORSESHOE OPERATING, INC.
Address: 110 W LOUISIANA STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2860	0	WITH 420 SX CMT
SURF	8.625	303		WITH 160 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/01/2016 12:30 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: PHELPS WHITE Company: HORSESHOE OPERATING Phone: (620) 874-8267

Proposed Plugging Method: PUMP DOWN 4 1/2" CASING WITH 150# HULLS & 185 SX CMT. FILL TO SURFACE & PRESSURE TEST TO 500#. ATTEMPT TO PUMP CMT DOWN ANNULUS.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/01/2016 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

FILL 4 1/2" CASING WITH CMT FROM 2816' TO 0' USING 200 SX CMT & 150# HULLS. PRESSURE TO 500#. HOLDING. PUMP 15 SX CMT DOWN THE ANNULUS TO 250#.

Top	Bot	Thru	Comments
2811	2816		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
JA

(TECHNICIAN)

RECEIVED
AUG - 4 2016
KCC DODGE CITY

Form CP-2/3

AUG 18 2016

no