

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20152-00-00  
Spot: SW Sec/Twnshp/Rge: 21-23S-41W  
1330 feet from S Section Line, 3986 feet from E Section Line  
Lease Name: DOYLE Well #: 1  
County: HAMILTON Total Vertical Depth: 2525 feet

Operator License No.: 4894  
Op Name: HORSESHOE OPERATING, INC.  
Address: 110 W LOUISIANA STE 200  
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2523	0	WITH 500 SX CMT
SURF	8.625	309		WITH 300 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/25/2016 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: PHELPS WHITE Company: HORSESHOE OPERATING Phone: (620) 847-8267

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/25/2016 7:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

STUCK GAS LIFT STRADDLE PACKERS AT 759' & 837' ISOLATING AT CASING LEAK BETWEEN 779' & 810'. INJECTION RATE DOWN 2 3/8" TBG AT 0.54 BPM AT 500# THROUGH A CASING LEAK (MUD ANCHOR PERFS ARE PLUGGED). PERFORATE 3 HOLES AT 1750'. INJECTION RATE DOWN TBG INCREASED TO 1 3/8 BPM AT 350#. ISIP-VACUUM. HAD CIRCULATION OUT 2 3/8" X 4 1/2" ANNULUS. CLOSE ANNULUS VALVE. INJECTION RATE 1/2 BPM AT 750#. ISIP-VACUUM (NOT SURE WHERE FLUID IS GOING). RAN 1" TBG TO 1720'. INJECTION RATE WITH WATER DOWN THE 1" WAS 3/4 BPM AT 1100#. SPOT 10 SX CMT PLUG AT 1720' @ 1/2 BPM @ 1000 PSI. HAD CIRCULATION OUT THE 1" X 2 3/8" ANNULUS. ISIP-VACUUM. PERFORATE 3 HOLES AT 950' & 3 HOLES AT 790'. CUT TBG OFF ABOVE TOP PACKER AT 700'. TIH WITH AD-1 PACKER ON 2 3/8" TBG TO 593'. INJECTION RATE WITH WATER 4 BPM AT 900#. ISIP-500#. PUMP 75 SX CMT THROUGH PERFS AT 950' & 790' AT 2 1/2 BPM AT 750 PSI. HOLDING 500#. TOOH WITH TBG & PACKER & RUN TBG TO 593'. CIRCULATE CMT TO SURFACE INSIDE THE 4 1/2" CASING WITH 30 SX CMT. TOOH WITH TBG & TOP OFF WITH 5 SX CMT. HOOK UP TO 4 1/2" X 8 5/8" ANNULUS & PUMP 20 SX CMT. PRESSURED TO 500#. HOLDING 200#.


Top	Bot	Thru	Comments
2448	2458		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
AUG - 4 2016  
KCC DODGE CITY

Form CP-2/3

AUG 18 2016

