



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION  
NOV 4 1970  
CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Holmstrom of K.N.N.G. has this

date requested permission to plug the following described well:

Mr. Holmstrom guarantees payment of the plugging fee.Operator's full Name: Kansas Nebraska Natural Gas Co., IncComplete Address: Box 608, Hastings, Nebraska 68901Lease Name: Kriete Well No. 1Location: SE SE NW Sec. 35 Twp. 24 Rge. 35 (E) (W)County: Kearny Total Depth 2700' Oil Well Gas Well X Input Well  SWD Well  D & A X Lost Hole Mr. Holstrom was instructed to plug the well as follows:10 3/4" to 498' circulated w/ cement. 7" to 2474' circulated w/ cement.5 1/2" liner 2468' to 2700' No perforationsPlug bottom w/ 120 sacks cement Top of cement 2204'Mud 2204' to 550' Spotted 30 sacks cement 550' to 400'Mud 400' to 50' Plug, Hulls & 10 sacks cement 50' to 0'.

Very truly yours,

  
Conservation Division Agent