



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 8 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Freeman of Garvey Drlg. Co. has this
date requested permission to plug the following described well:

Mr. Freeman guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: 300 W. Douglas Wichita, Ks

Lease Name: Parkin C Well No. 1

Location: C SE/SW Sec. 8 Twp. 30s Rge. 18 (E)(W) W

County: Kiowa Total Depth 5100 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Freeman was instructed to plug the well as follows:

533 ft of 8 5/8 surface pipe cemented with 400 sacks. Pump
30 sacks cement to 530 ft. Fill hole to 45 ft, plug, 1/2 sack
hulls, 15 sacks cement to surface. 2 sacks cement in rat
hole. 2 sacks cement in mouse hole.

Globe Cementing Co. Great Bend, Ks

Very truly yours,

D. Russell Babinster
Conservation Division Agent