

15-009-01559-0000

State of Kansas



FORM - CP-2  
Rev. 8-26-62

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 29 1964  
6-29-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Herman Geo. Kaiser of Herman George Kaiser has this date requested permission to plug the following described well:

Mr. Herman George Kaiser guarantees payment of the plugging fee.

Operator's full Name: Herman George Kaiser

Complete Address: 909 Palace Bldg., Tulsa, Oklahoma

Lease Name: Esfield "C" Well No. # 2

Location: SE SW NE Sec. 7 Twp. 16 Rge. 11 (E) (W) W

County Barton Total Depth 3257 Oil Well X

Gas Well     Input Well     SWD Well     D & A     Lost Hole    

Mr. Albert Unruh was instructed to plug the well as follows:

8 5/8" 254' Cwc.

Sanded hole back to 3240' & dumped 5 sax cement with  
dump bailer. Pulled pipe; bailed hole dry to 240'; set  
rock bridge; displaced 25 sax cement. Mud to 40'; set rock  
bridge & displaced 10 sax cement, cementing to base of  
cellar.

Very truly yours,  
Don Truman