

15-009-06253-0000

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 4 1963

6-4-63

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts.  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Milton Corley of H-30 Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Herman G. Kaiser guarantees payment of the plugging fee.

Operator's full Name: Kaiser-Francis

Complete Address: 909 Palace Bldg., Tulsa 3, Oklahoma

Lease Name: Staudinger Well No. # 1

Location: S/2 NE SW Sec. 7 Twp. 16 Rge. 11 (E) (W)

County Barton Total Depth 3320 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Milton Corly was instructed to plug the well as follows:

8 5/8" 305' Cwc.

Filled hole with heavy mud to 300', set plug with 1/4 sax hulls, & displaced 25 sax cement thru drill pipe.

Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Don. Truman  
Conservation Division Agent